WORKFLOW

Coal Dispatch from Mine to Railway Siding (Road Transport)

STEP 1: VEHICLE AUTHORIZATION & ENTRY INTO MINE

- All vehicles are **pre-authorized in the internal system**.
- Each vehicle is **GPS-enabled** and monitored **24×7** from the Control Room.
- Vehicle is allowed entry only after system validation.

STEP 2: GATE PASS / LOADING SLIP ISSUE

- On entry, vehicle must **handover the previous trip gate pass**.
- **New gate pass / loading slip** is issued **only after verification** of previous trip completion.
- This ensures:
    - No duplicate trips
    - No unauthorized lifting

STEP 3: MOVEMENT TO LOADING POINT

- Authorized vehicle proceeds directly to the **coal loading point**.
- Vehicle stands in **queue as per operational sequence**.
- No diversion or intermediate stoppage allowed inside mine.

STEP 4: COAL LOADING AT MINE

- Coal is loaded by **designated loader operators**.
- Operators ensure:
    - No overloading
    - No underloading
- Loading is done strictly as per **permitted carrying capacity**.

STEP 5: WEIGHBRIDGE MOVEMENT & WEIGHMENT

- After loading, vehicle moves to the **weighbridge**.
- Weighment is carried out and **weighment slip is generated**, containing:
    - Gross weight
    - Tare weight
    - Net coal weight

STEP 6: MINING CHALLAN GENERATION (JIMMS)

- Based on:
    - Weighment slip
    - Approved route (Mine → Railway Siding)
- **Mining challan is generated in JIMMS portal**.
- Challan is linked to:
    - Vehicle number
    - Quantity
    - Destination siding

STEP 7: DUST SUPPRESSION & SAFETY COMPLIANCE

- Loaded vehicle passes through **water sprinklers** to suppress dust.
- After sprinkling:
    - Entire vehicle body is **covered with tarpaulin**
- Ensures:
    - Environmental compliance
    - Road safety

STEP 8: EXIT INSPECTION & VERIFICATION

- At mine exit point:
  - Weighment slip is verified
  - Mining challan is verified
- Physical inspection ensures:
  - Proper tarpaulin covering
  - No spillage risk

STEP 9: EXIT FROM MINE PREMISES

- After successful verification:
  - Vehicle is allowed to **exit the mine**
- Trip is marked as **active** in the system.

STEP 10: GPS-BASED TRANSIT MONITORING

- Vehicle movement is tracked **live through GPS**.
- Control Room monitors:
  - Route adherence
  - Stoppage or deviation
  - Speed and delay

STEP 11: DRIVER INSTRUCTIONS & ROAD DISCIPLINE

- Drivers are **strictly instructed**:
  - Not to stop vehicles en-route
  - To follow approved route only
- Any deviation or abnormal stoppage is flagged.

STEP 12: ROAD PATROLLING & SAFE ARRIVAL

- Dedicated **road patrolling teams** monitor vehicle movement.
- Ensures:
  - Timely arrival at railway siding
  - Safety and security of coal
- Vehicle reaches siding for **shift-wise receipt entry**.